

SARPOL SET UP SPECIFICATIONS & BOQ Page :1/3

SUPPLIERS ARE REQUESTED TO SUBMIT THEIR OFFER TO IRMRA ADDRESSING TO "THE DIRECTOR IRMRA" AND MENTIONING THE SUBJECT OF QUOTATION ON THE ENVELOPE BY 18.08.2017 TILL 17:HRS. AT BELOW MWNTIONED ADDRESS.

IRMRA 254/1B ROAD No. 16 V , Wagle Estate, Thane West : 400604

Sr.No.	Description	Quantity	Rate(Rs.)	Amount(Rs.)
1	Partition Work with 2" x 1 1/2" wooden post, runner, 6mm Ply both side after the 1mm laminate pasting, 4mm clear glass fixing if required etc	588.17 sft		
2	Charges for the painting work at chemical lab room's wall, ceiling, pillar, etc. with approved color & brand before two coats of primer.	3692 sft		
3	Charges for making & fixing Machine Table as per your direction. 3'-0" x 3'-0" x 2'-6" x 1 no. 4'-0" x 3'-0" x 2'-6" x 1 no. 6'-6" x 3'-0" x 2'-6" x 1 no.	33.75 sft.		
4	Providing & making computer table as per your specification with % ply, 1 mm laminate, drawer, tea tray, cupboard, keyboard tray, etc. complete. Charges for making & fixing Door at Chemical	3 Nos.		
5	Lab room with IS1 marked Flush Door, 1mm Laminate, Door Closure, Lock, Door Stopper with all other related materials.	3 Nos.		
6	Charges for making wooden partition at above area with 2" X 1.5" wooden Post, Runner, 6mm Ply, 1mm Laminate, Wooden bit, 4mm clear glass if required etc.complete	401.29		
7	Providing false ceiling at above with local channel, Parameter, angle, hook, Fastener, etc. with all other related materials after that 12mm Gyp Board & two coats of Top Coat, complete.	407.36		
8	Providing, making & fixing Door at Wet Lab Entrance with Flush Door, 1mm Laminate, Door Closure, Door Stopper, Lock, etc.	2 Nos.		
9	Charges for providing & making above Partition with 2" x 1" Wooden Post, Runner, 6mm Ply, 1mm Laminate 4mm Clear Glass where require & all other related materials, complete.	580 Sft.		
10	Providing, laying & fixing Lan line at your proposed chemical lab's cabin with 3 Nos. UPS line, 9U rack, switch, 24 Port Panel, Socket with box, Cat 6 wire etc. with all other related materials for the line fixing.	1727 Sft.		
11	Providing, making & fixing false ceiling at chemical lab	1686 Sft.		
12	Charges for making & fixing wooden Partition at above premises of Physical Lab	588 Sft.		
13	Providing & fixing false partition with 2" X 1" W wooden post, runner, 6mm Ply both side after that 1mm laminate pasting, 4mm clear glass fixing if required etc. complete at rest of the Physical Lab.	580 sft.		

SARPOL SET UP SPECIFICATIONS & BOQ Page : 2/3

SUPPLIERS ARE REQUESTED TO SUBMIT THEIR OFFER TO IRMRA ADDRESSING TO "THE DIRECTOR IRMRA" AND MENTIONING THE SUBJECT OF QUOTATION ON THE ENVELOPE BY 18.08.2017 TILL 17:00 HRS. AT BELOW MENTIONED ADDRESS.

IRMRA 254/1B ROAD No. 16 V , Wagle Estate, Thane West : 400604

Sr.No.	Description	Quantity	Rate(Rs.)	Amount(Rs.)
14	Wooden partition, 2" X 1"W wooden post, runner, 6mm Ply pasting both side after the 1mm laminate pasting, 4mm clear glass fixing if required etc. complete at the Proposed Training Room of above Premises.	580 sft		
15	Providing wooden partition at rest of the Training Room at above premises.	580 sft		
16	Providing & fixing Door for Training Room, Br. Head's room, Officer's Cabin, etc. with Flush Door, 1mm Laminate, Door Closure, Door Lock, Door Stopper, etc. related materials, complete.	05 Nos.		
17	Charges for false ceiling with decorative margin on edge of ceiling for Br. head room at above complete. Providing Painting with approved Brand &	408 Sft		
18	Providing Painting with approved Brand & Colour with Distemper or Plastic Emulsion Paint before the coat of Primer.	3,224 Sft		
19	Providing & making false partition at Br. Head chamber at above premises with 2." X 1.25" wooden post, runner, both side 6mm ply, laminate, etc. complete.	578 Sft.		
20	Providing & making false ceiling at Trg. Room / Conference Room at above complex with Decorative design.	1227 Sft		
21	Charges for making computer line at Branch Head Room & Trg. Room with 9 U Rack, switch, socket box, Cat 6 Wire etc. with all other related materials for the line fixing etc.	900 Sft.		
22	Providing, making & fixing Trg. Room/ Conference Table as per Direction up to 24 seater approximately at above complex	1 No.		
23	with Ply, Wood, Laminate, etc. Charges for making & fixing Table for Trg. Co-coordinator with Ply, Laminate & all other related materials with side table.	1 No.		
24	Charges for making & fixing Br. Head Table with side table by Ply, Laminate etc. & all other related materials.	1 No.		
25	Charges for Rest of the area painting with approved color & brand with Distemper / Plastic emulsion but existing Door & Steel Window will be synthetic enamel paint before two coat of primer at above complex.	5990 Sft.		
26	Charges for providing internal B.S.N.L. line up to first floor Joint Box area all other related materials & intercom.	L.S.		

SARPOL SET UP SPECIFICATIONS & BOQ Page : 3/3

SUPPLIERS ARE REQUESTED TO SUBMIT THEIR OFFER TO IRMRA ADDRESSING TO "THE DIRECTOR IRMRA" AND MENTIONING THE SUBJECT OF QUOTATION ON THE ENVELOPE BY 18.08.2017 TILL 17:00 HRS. AT BELOW MENTIONED ADDRESS.

IRMRA 254/1B ROAD No. 16 V , Wagle Estate, Thane West : 400604

Sr.No.	Description	Quantity	Rate(Rs.)	Amount(Rs.)
27	Providing & supplying semi executive chair for Br. Head Cabin & Training Room Head with high neck back rest, arm & revolving as per manufacturer's specification.	2 Nos.		
28	Charges for supplying staff seating chair for Lab. Co-coordinator, Training Co-coordinator etc.	8 Nos.		
29	Charges for supplying chair for Training Room.	25 Nos.		
30	Providing,making & fixing Electrical work, including Speet A/C. LED Lamp, Fan, Exhaust Fan etc. with	L.S.		