

IRMRA/RFQ/2021-22/49

23.03.2022

Sealed Quotations are invited by 30.03.2022 upto 13.00 Hrs for Civil Repair works in Banberry Building room at IRMRA, as per below Specifications:

<b>A) Waterproof IPS works inside Banberry Building at IRMRA.</b>			
<b>Sr.No.</b>	<b>Description of works</b>	<b>Qty</b>	<b>Unit</b>
1	Dismantling of existing pedestal/platform and surface preparation of the existing flooring in order to receive the new flooring treatment.	450	Sqft
2	IPS Flooring Inside: 75 mm thick cement concrete flooring with concrete hardner topping, under layer of 60 mm thick cement concrete 1:2:4 and top layer of 12-15 mm thick cement hardener consisting of mix 1:2 hardening compound mixed @ 2 ltr per 50 kg of cement or as per manufacturers specifications.	425	Sqft
3	Providing first class Burnt Brick masonry of 4" thick with conventional/ I.S. type bricks in cement mortar 1:4 for drain in store room.	50	Sqft
4	Providing cement plaster 15-18 mm thick in cement mortar 1:5 with neat finishing, with addition of waterproofing compound in cement of approved make and manufacturer and curing etc. complete.	100	Sqft
5	Removing, cutting, refixing of existing MS door shutter	L.S	L.S

Continue.....2 page

<b>B ) Structural Repair works in Banberry Building at IRMRA.</b>			
<b>Sr.No.</b>	<b>Description of works</b>	<b>Qty</b>	<b>Unit</b>
	<b>Structural Repair works in Banberry store room at IRMRA.</b>		
1	Carefully dismantling and removing existing loose damaged surface to get square or rectangular shape using chisel and hammer so as to expose concrete surface as per requirement and as directed for. The rate shall include all tools and tackles, labour charges, cleaning etc.	200	Sqft
2	Repairing loose / cracked / damaged RCC members dismantled as per item no. 1 above with Applying Rust Remover on corroded steel bar, applying bond coat and polymer modified cementations mortar treatment at all height and level including scaffolding, taking away debris from the premise etc.	200	Sqft
3	Providing cement plaster 15-18 mm thick in cement mortar 1:5 with neat finishing, with addition of waterproofing compound in cement of approved make and manufacturer and curing etc. complete.	200	Sqft
5	Providing and Applying Birla white Putty over newly plastered area.	150	Sqft
6	Providing and applying 2 coats of Acrylic Distemper over a coat of Primer on internal walls and ceiling after preparation of surface etc	1000	Sqft

**Payment** – Within 30 days from the date of Invoice & satisfactory completion of works

**Sealed quotation should be in the name of:**

**The Director**

Indian Rubber Manufacturers Research Association (IRMRA)  
(Affiliated to Ministry of Commerce and Industry, Govt. Of india)  
Plot No: 254/1B, road No.16V,  
Wagle Industrial Estate,  
Thane (W)-400604.  
Contact No: 022-67873244.

**On the Envelope please mention “Quotation for Civil Repair works in Banberry Building room at IRMRA”**